



# THE COMPLETE LONDON WET ROOM PLANNING GUIDE

*A detailed PDF covering budgeting, waterproofing, drainage, maintenance, and renovation planning.*

## 1. BUDGETING & COST CONTROL

- **Premium Tanking Allocations:** Dedicate 30-35% of your total budget to dynamic multi-layer waterproofing, specialized membranes, and floor leveling.
- **Structural Subfloor Rigidity:** Allow contingency funds for installing thick marine plywood overlays or structural cement boards to eliminate bounce.
- **High-End Hardware:** Reserve budget for high-capacity linear drains and sleek, frameless glass shower guards.

## 2. MULTI-LAYER WATERPROOFING (TANKING)

- **Continuous Barrier Systems:** Apply liquid-applied tanking membranes across the entire floor area, extending up walls to a minimum height of 2 metres.
- **Joint and Corner Reinforcement:** Integrate heavy-duty elastomeric joint tape on all wall-to-floor junctions and drainage perimeter flanges.
- **Curing Integrity:** Ensure multi-stage structural layers are completely dry and tested before introducing surface tiling.

## 3. ADVANCED DRAINAGE INFRASTRUCTURE

- **Precision Floor Gradients:** Create a steady 1:40 to 1:50 structural slope toward the waste outlet to completely prevent standing water.
- **High-Flow Linear Channels:** Select luxury linear drains capable of managing up to 30–40 litres of water flow per minute to match high-pressure systems.
- **Under-Floor Clearance:** Ensure floor joists can easily house a low-profile trapped waste pipe without cutting into structural supports.

## 4. TILING & MAINTENANCE ROUTINES

- **Anti-Slip Material Selection:** Specify high-grade textured porcelain or natural stone with an 'R11' anti-slip safety rating.
- **Epoxy Grout Protection:** Use water-impermeable epoxy grout to eliminate moisture absorption, staining, and surface mold.
- **Underfloor Heating Synergy:** Install underfloor heating mats to accelerate surface evaporation and keep the floor dry and comfortable.

## 5. WET ROOM CONSTRUCTION PHASES

---

- **Phase 1 — Stripping & Structural Framing:** Deep extraction of old fittings, inspecting structural timber, and reinforcing floor joists.
- **Phase 2 — Drainage Positioning & Sloped Formers:** Installing specialized sloped wet-room trays and plumbing high-capacity waste routes.
- **Phase 3 — Advanced Tanking & Waterproof Testing:** Applying professional tanking membranes followed by rigorous 24-hour flood testing.
- **Phase 4 — Precision Tiling & Hardware Fit-Out:** Aligning large-format tiles, applying epoxy grout, and mounting premium brassware.

Ready to integrate a seamless, spa-like wet room into your home? Contact our premium layout design and structural installation team today.

**Phone:** 0745 666 6389

**Email:** [cgbathroomslimited@gmail.com](mailto:cgbathroomslimited@gmail.com)