



CG Bathrooms Limited
Casicas Glenn Bathrooms estd. 2004

CG Bathrooms Limited
cgbathroomslimited.co.uk
Phone: 0745 666 6389
cgbathroomslimited@gmail.com

FREE PDF CHECKLIST

BATHROOM INSTALLATION PREPARATION CHECKLIST

A printable step-by-step checklist showing everything homeowners should prepare before a bathroom installation begins, helping reduce delays and unexpected costs.

1. PRE-START FIXTURE & MATERIAL VERIFICATION

- ☐ **Delivery Verification & Damage Inspection:**
Unpack and inspect all sanitaryware, glass screens, taps, and tiles at least 48 hours prior to start date. Ensure no chipped porcelain, hairline cracks, or missing fittings.
- ☐ **Tile Quantity & Batch Number Matching:**
Verify you have a 10–15% tile overage for cuts/wastage and confirm all boxes share identical shade and batch numbers to prevent color mismatching.

2. SITE PROTECTION & TRADESPERSON ACCESS

- ☐ **Clear Access Route & Floor Protection:**
Clear hallways, staircases, and entryways. Lay heavy-duty floor protection film or correx sheets from the main door to the bathroom.
- ☐ **Staging & Storage Area Assignment:**
Designate a dry, secure ground-floor area (garage or spare room) for installers to store tools, new fixtures, and adhesive bags during the build.

3. UTILITY ISOLATIONS & PLUMBING CHECKS

- ☐ **Main Stopcock & Utility Location:**
Locate and test your primary water stopcock and consumer unit (fuse box). Ensure isolation valves function smoothly before strip-out begins.
- ☐ **Temporary Water & Facilities Plan:**
Confirm arrangements for alternative toilet and washing facilities while main water lines are isolated during rough-in stages.

4. WASTE MANAGEMENT & PERMITS

- ☐ **Skip Hire & Parking Permit Clearance:**
Arrange driveway access or secure local council permits for skip placement/trade parking on public roads prior to Day 1 demolition.

5. DAY-ONE TRADES BRIEFING & SIGN-OFF

- ☐ **Layout & Height Marking Sign-Off:**
Walk through the room with your Lead Fitter. Re-confirm shower valve eye-levels, towel rail placement, niche heights, and tile layout direction.
- ☐ **Part P Electrical & Tanking Sign-Off Confirmation:**
Confirm schedule for mid-way waterproofing inspection and Part P electrical certification before walls are closed up with boards.

Preparing for your bathroom installation? Let CG Bathrooms Limited handle it seamlessly.

Call 0745 666 6389 or email cgbathroomslimited@gmail.com | cgbathroomslimited.co.uk